

SUNLAND WATER DISTRICT

APPLICATION FOR SIDE SEWER PERMIT

Permit No. _____

Date: _____

Owner: _____ Contractor: _____

House Address _____

Basement: Yes ____ No ____

Lot No. _____

Block No. _____

Division No. _____

FEES DUE:

Permit Fee \$10,000.00

Latecomer Charges _____

TOTAL DUE: _____

I hereby certify that the above connection has been made and inspected and the connection has been made as shown on the attached drawing.

(SWD or authorized representative)

Date

SERVICE CHARGES START AS FOLLOWS:

Billings for sewer service shall be rendered as follows for all customers:

For buildings, residences, or home sites constructed in SunLand, charges shall begin the date of connection to the District's system. If the connection occurs before the 15th of the month, the full applicable monthly charges shall be charged. If the connection occurs after the 15th of the month, one half of the applicable charge shall be charged.

The date of connection will occur upon inspection by the District of the completed side sewer before backfilling and upon the Applicant obtaining a Side Sewer Permit and paying the required fee.

Monthly charges for water service will commence upon connection to the sewer system.

SUNLAND WATER DISTRICT

APPLICATION FOR SIDE SEWER PERMIT

The undersigned hereby applies for permission to construct a side sewer as indicated on the preceding page.

The undersigned hereby agrees to construct a side sewer as above applied for subject to the following stipulations:

1. That all regulations and requirements set forth by the Side Sewer Resolution and any amendments thereto, of the Water District, be complied with fully and completely. Said Resolution by this reference is included in its entirety as a part of this side sewer permit application and the issuance of this permit and acceptance by the Owner, or his agent, will be construed as prima facie evidence that the Owner, or his agent, have read same agree to its terms and stipulations in their entirety.
2. The Owner hereby agrees to maintain the side sewer constructed under this permit in accordance with the rules and regulations of the SunLand Water District and, further, will permit access with entry by authorized representatives of the Water District on the property described in this permit at any reasonable time for the purpose of examination for compliance with all Sewer District regulations.
3. The Owner is hereby notified that the SunLand Water District sewerage system is of the sanitary type system and he agrees that he will not at any time connect storm water drainage from any source to the District's system. This includes, but is not limited to the following:
 - a. Roof Downspouts
 - b. Building Footing Drains
 - c. Springs on the Property
 - d. Any Outside Ground Water Drains
4. The Owner and his Contractor hereby agree to accept full responsibility, and to hold SunLand Water District harmless, for any liability, damage and/or costs which may accrue from prosecution of side sewer work under this permit.
5. The Owner and his Contractor hereby agree to safeguard the work done under this permit in such a manner as to prevent injury and/or damage to the public. Such precautions shall include the employment of all necessary ditch safeguards such as lanterns, barricades, and safe access or egress through the working area. The Owner, and/or his Contractor, hereby agree to meet all applicable OSHA and WISHA regulations in the performance of this side sewer installation.
6. The Owner and/or his Agent agrees to employ a side sewer contractor approved by the District and covered with adequate and satisfactory liability insurance, licensed by the State of Washington, for all work to be prosecuted on public roads and rights-of-way. The Owner may provide some or all of the required construction upon his property per the District's Standard Specifications and Inspection Procedures.

7. The Owner and his Contractor agree to install the side sewer covered by this permit in full compliance with the sketch entitled, "Side Sewer Requirements," which includes, but is not limited to the following:
 - a. A clean out shall be required at the point of connection with the side sewer stub.
 - b. Sewer pipe covers on provide property to be at least 18 inches.
 - c. Minimum grade to be 2% unless special construction techniques are used per the Side Sewer Resolution.
 - d. No bends sharper than 45 degrees will be permitted without a clean out, and no group of bends totaling 90 degrees or more will be allowed without a clean out.
8. No backfilling will be allowed until the work has been reviewed and approved by the District's authorized representative. All backfill shall be tamped and/or water settled.
9. The Owner and his Contractor agree that all street cleanup and road restoration will be made to the satisfaction of the governing authority, i.e., City County, or State Highway, etc.
10. The Owner and Contractor agree to obtain at no cost or obligation to the District, all other necessary permits for construction work to be accomplished under this permit.

OWNER'S SIGNATURE _____

Date _____

or OWNER'S AUTHORIZED AGENT: _____

CONTRACTOR'S SIGNATURE: _____

Date: _____

AUTHORIZATION: _____

By Water District

Date: _____