

# SUNLAND WATER DISTRICT

## Commissioners Meeting

December 2024

### Managers' Report by Tim Berger

#### Water Reclamation Facility

- 12/9/24 Utility Services completed electrical work on the Main Lift Station radar system installation. The new radar and backup float system are working in unison. A new bypass pump has been ordered.
- 11/25/24 – 103 Olympus Ct. – Rocky found a roof drain dumping into a 4” drain pipe and possibly into our sewer manhole. We are still investigating. Drainage from this cul de sac appears to also be draining in the manhole. We will be installing a 4-inch manhole riser ring. All this water then dumps into the new Fawnwood Lift Station.
- A new air monitor for the Main Lift Station vault is onsite, Installation is being scheduled with Angeles Electric.
- 12/4/24 Willy & Rich successfully installed the new 3- way valve from the digesters to the sludge basin.
- 12/19/24 – Ethan from Vega coming out to train our crew on the new Main Lift Station radar system.

#### Water

- 12/3/24 The Upper Reservoir epoxy job is complete. Purcell Coatings did an excellent job.
- 12/12/24 The Upper Reservoir was cleaned, disinfected and back in service – 1 cell.
- 11/27/24 – The Water Crew replaced a 4-inch non- functional gate valve off the effluent pipe on the upper reservoir well pump. (Monthly in-house coliform sample site).
- The new office-site fire hydrant is here. Installation is planned sometime after New Year's.
- Karen and Rocky worked together and purchased 7 new – 2-inch water meters that are capable of reading hourly flows for \$600.00 each; a substantial savings over the regular price of \$1400.00 each.
- There was a water service line leak at 117-A Hilltop Drive on a private road. Scott came in for a couple hours to oversee excavation.
- 12/2/24 – DOH has approved funding for the second round of PFAS testing in late February 2025.
- Water loss held steady at 5% for the month.
- 12/10/24 Passed all coliform tests for the year thanks to Rock's sampling expertise.