



## **Commissioner's Meeting March 17, 2026**

### **MANAGERS' REPORT BY ROBERT WHALEN**

#### **Water Reclamation Facility**

- Nailed IT Construction has nearly completed the roof replacement at the Treatment Plant.
- Angeles Electric has completed all electrical work.
- High Tech Security has installed new motion sensors and a door alarm for the new building.
- Willy installed new turbidimeter. Old one has been sent off to see if it is able to be repaired for a viable spare.
- Annual Bio-solids report is due March 1<sup>st</sup> and was submitted in February.

#### **Water**

- Lower reservoir has been cleaned and is ready for the upcoming irrigation season.
- Rocky and Dave have been out with our new GIS device and are making good progress at accurately mapping the utilities out in the field.
- Crew repaired water service line leak at 179 Sunset place. Service line will be replaced later this year. Estimated water loss with 1/8-inch hole at 80 PSI = 4,205gpd or 46,255 gallons over 11 Days from report of leak In February.
- Crew responded to a hit utility on Williams Place, after-hours repair was made on the service line with the help of the PUD. Line was damaged while PUD was boring underground utilities. Line was temporarily shut down while work was being conducted. Two (2) ¼-inch holes in water line at 80 PSI leaked for approximately 2 hours = 11.67gpm = 1,400 estimated water loss. Will be accounted for in March's water loss calculations.



- Utility Services have been scheduled for March 24<sup>th</sup> to start upper reservoir well pump replacement. Reservoir cleaning will commence at the same time.
- Water loss for the month of February was 10%. Static levels for February----  
-----rests at 90.5ft, while the pumping levels are at 118.ft.